



LOT 4 PRESSURIZED IN-GROUND WASTEWATER DISPOSAL SYSTEM PLAN VIEW DETAIL

SCALE: 1-INCH = 5- FEET




FLUSHING RISER DETAIL

NOT TO SCALE



ORIFICE SHIELD DETAIL


NOT TO SCALE



- NOTES:
1. SEPTIC TANK SHALL BE SET LEVEL ON A MINIMUM OF SIX INCHES OF COMPACTED GRANULAR BASE.
 2. AN INLET TEE Baffle IS REQUIRED.
 3. IF WATER-PROOF BOOTED CONNECTIONS ARE NOT USED, ALL PIPE PENETRATIONS SHALL BE SEALED WITH "WATER PLUG" NON-SHRINK HYDRAULIC CEMENT.
 4. EFFLUENT FILTER ACCESS SHALL BE COMPLETED FLUSH WITH FINISH GRADE.


1,500 GALLON TOP-SEAM CONCRETE SEPTIC TANK

NOT TO SCALE



LOT 4 PRESSURIZED IN-GROUND WASTEWATER DISPOSAL SYSTEM SECTION DETAIL


SCALE: 1-INCH = 2- FEET



- NOTES:
1. PUMP STATION SHALL BE SET LEVEL ON A MINIMUM OF 6-INCHES OF COMPACTED GRANULAR BASE.
 2. PUMP STATION SECTIONS SHALL HAVE BUTYL RUBBER JOINT SEALER.
 3. IF WATER-PROOF BOOTED PIPE CONNECTIONS ARE NOT USED, PIPE PENETRATIONS SHALL BE SEALED WITH "WATER PLUG" NON-SHRINK HYDRAULIC CEMENT.
 4. ON/OFF FLOAT SWITCH TO BE SET WITH A 7 INCH SWING SETTING TO PROVIDE A 150 GALLON DOSE VOLUME.
 5. HIGH WATER LEVEL ALARM AND PUMP STATION SHALL BE WIRED BY A LICENSED ELECTRICIAN.
 6. THE HIGH WATER ALARM SHALL BE MOUNTED AT A VISIBLE LOCATION.
 7. THE EFFLUENT PUMP SHALL BE CAPABLE OF 37 GPM VS. 33 TDH.

1,000 GALLON TOP-SEAM CONCRETE PUMP STATION

NOT TO SCALE



GRASSED AREA PIPE IN TRENCH DETAIL

NOT TO SCALE

PRESSURIZED IN-GROUND WASTEWATER DISPOSAL SYSTEM CONSTRUCTION AND MAINTENANCE NOTES

1. THE PRESSURIZED IN-GROUND WASTEWATER DISPOSAL SYSTEM SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE STATE OF VERMONT, AGENCY OF NATURAL RESOURCES, ENVIRONMENTAL PROTECTION RULES, CHAPTER 1, WASTEWATER SYSTEM AND POTABLE WATER SUPPLY RULES.
2. THE PRESSURIZED IN-GROUND WASTEWATER DISPOSAL SYSTEM LOCATION SHALL BE STAKED OUT BY THE DESIGNER PRIOR TO START OF CONSTRUCTION.
3. THE DESIGNER SHALL BE NOTIFIED AT LEAST 48 HOURS IN ADVANCE FOR INSPECTIONS OF THE SEPTIC TANK, PUMP STATION AND PREPARATION OF THE ABSORPTION TRENCHES PRIOR TO PLACING THE SYSTEM STONE AND PRIOR TO FINAL COVERING OF THE WASTEWATER SYSTEM.
4. THE DESIGNER SHALL BE NOTIFIED AT LEAST 48 HOURS IN ADVANCE FOR A PRESSURE TEST OF THE IN-GROUND SYSTEM PRESSURE DISTRIBUTION NETWORK.
5. THE CONTRACTOR SHALL ADHERE TO VERMONT OCCUPATIONAL HEALTH AND A SAFETY GUIDELINES FOR EXCAVATING AND TRENCH EXCAVATIONS.
6. SEPTIC TANK EFFLUENT FILTER SHOULD BE REMOVED AND RINSED BACK INTO THE SEPTIC TANK ONCE A YEAR.
7. THE SEPTIC TANK AND PUMP STATION SHALL BE INSPECTED ANNUALLY AND PUMPED OUT EVERY 3 YEARS.
8. FOLLOWING THE PRESSURIZED IN-GROUND WASTEWATER SYSTEM INSTALLATION, FINISH GRADE SHALL BE SEEDED AND MULCHED WITH A CONSERVATION GRASS SEED MIX.
9. WATER SOFTENER BACKWASH, SEPTIC TANK ADDITIVES, GREASE OR SANITIZERS SHALL NOT BE INTRODUCED INTO THE WASTEWATER DISPOSAL SYSTEM.

SIGNATURE:

 JASON S. BARNARD
 LICENSED DESIGNER #126178

DATE	DESCRIPTION	BY
REVISIONS		
FOUR-LOT SUBDIVISION 167 Main Street, P.O. Box 820, Hinesburg, VT 05450 Telephone: (802) 933-5168		
DAVID CHARLES NAGEL REVOCABLE TRUST & HELEN FINNELL NAGEL REVOCABLE TRUST GILMAN ROAD, HINESBURG, VERMONT LOT 4 WASTEWATER SYSTEM DETAILS AND NOTES		
THESE PLANS WITH LATEST REVISIONS SHOULD ONLY BE USED FOR THE PURPOSE SHOWN BELOW: <input type="checkbox"/> PRELIMINARY DRAFT <input checked="" type="checkbox"/> FINAL STATE REVIEW		
PROJECT NO. 21389	DATE: 08-30-2022	SCALE: AS NOTED
SURVEY: OL, TG, AW	DRAWN: SB	CHECKED: JSB
DRAWING NO. D-4	SHEET 9 OF 9	