

STANDARD EPSC PLAN REQUIREMENTS

THIS SECTION CONTAINS THE MINIMUM REQUIRED ELEMENTS FOR THE EROSION PREVENTION AND SEDIMENT CONTROL PLAN. THESE ELEMENTS ARE IN ADDITION TO THE SITE SPECIFIC EROSION PREVENTION AND SEDIMENT CONTROL PRACTICES SHOWN ON THE PLANS.



- EROSION PREVENTION**
 - PROGRESSIVE CONSTRUCTION. THE AREA OF SOIL DISTURBANCE SHALL BE LIMITED TO THOSE AREAS THAT CAN BE ACTIVELY WORKED AND MANAGED WITH THE FORCES AVAILABLE. AREAS THAT ARE NOT ACTIVELY BEING WORKED FOR A PERIOD OF 5 DAYS OR MORE SHALL BE TEMPORARILY STABILIZED.
 - THE MAXIMUM AREA FOR SOIL DISTURBANCE AT ANY ONE TIME ON THE ENTIRE PROJECT SITES SHALL NOT EXCEED 10% OF THE TOTAL SITE AREA.
 - SEEDMENT BASINS, SEDIMENT TRAPS, PERIMETER CHECKS, SEDIMENT BARRIERS, AND OTHER MEASURES INTENDED TO TRAP SEDIMENT SHALL BE CONSTRUCTED AS A FIRST STEP IN ANY LAND-USE DISTURBANCE ACTIVITY AND SHALL BE MADE FUNCTIONAL BEFORE UPLAND LAND DISTURBANCE TAKES PLACE.
 - CONCENTRATED RUNOFF SHALL NOT FLOW DOWN CUT OR FILL SLOPES UNLESS CONTAINED WITHIN AN ADEQUATE TEMPORARY OR PERMANENT CHANNEL, FLUME, OR LAKE DRAIN STRUCTURE.
 - WHENEVER WATER SEEPS FROM SLOPE FACE, ADEQUATE DRAINAGE OR OTHER PROTECTION SHALL BE PROVIDED.
 - BEFORE NEWLY CONSTRUCTED STORMWATER CONVEYANCE CHANNELS OR PIPES ARE MADE OPERATIONAL, ADEQUATE OUTLET PROTECTION AND ANY REQUIRED TEMPORARY OR PERMANENT CHANNEL LINING SHALL BE INSTALLED IN BOTH THE CONVEYANCE CHANNEL AND THE RECEIVING CHANNEL.
- UNDERGROUND UTILITY LINES SHALL BE INSTALLED IN ACCORDANCE WITH THE FOLLOWING STANDARDS IN ADDITION TO OTHER APPLICABLE CRITERIA.
 - NO MORE THAN 60 LINEAR FEET OF TRENCH MAY BE OPENED AT ONE TIME.
 - EXCAVATED MATERIAL SHALL BE PLACED ON THE UPHILL SIDE OF TRENCHES.
- ALL SEDIMENT REMOVED FROM SEDIMENT CONTROL PRACTICES AS A PART OF MAINTENANCE SHALL BE DISPOSED OF IN AN AREA THAT IS:
 - LESS THAN 10% SLOPE.
 - AT LEAST 100 FT. FROM ANY DOWNSLOPE WATER BODY OR CONVEYANCE TO A WATER BODY (INCLUDING STORM DRAIN INLET OR DITCH).
 - VEGETATED. PERMANENT STABILIZATION OF SEDIMENT SHALL BE IMMEDIATELY IMPLEMENTED FOLLOWING DISPOSAL.
- FOR ANY AREA TO BE STABILIZED FOR WINTER BY VEGETATIVE COVER, SEEDING MUST BE COMPLETED LATER THAN SEPTEMBER 15.
- ANY AREA TO BE STABILIZED FOR WINTER THAT DOES NOT HAVE ESTABLISHED VEGETATION BY OCTOBER 15 MUST BE STABILIZED BY ANCHORED MULCH AT THE WINTER APPLICATION RATE OF 4 TONS PER ACRE. OTHER APPROVED STABILIZATION MEASURES (E.G. ROLLED EROSION CONTROL PRODUCT), DOMANT SEEDING (E.G. WITH WINTER ICE) IS RECOMMENDED.
- DISTURBED AREAS BORDERING AND DRAINING TO ROADS MUST HAVE AN APPROPRIATE SEDIMENT BARRIER SPANNING THE EDGE OF THE DISTURBANCE TO PREVENT WASHING OF SEDIMENT ONTO ROADWAYS OR INTO ROAD DITCHES.
- HAY MULCH SHALL BE APPLIED AT A MINIMUM RATE OF 2 TONS PER ACRE. HAY MULCH APPLICATION DURING WINTER CONSTRUCTION SHALL BE AT A RATE OF 4 TONS PER ACRE. WHERE SUBSALINE SOILS ARE ENCOUNTERED, MULCH SHALL BE APPLIED BY TRACKING WITH EQUIPMENT (WITH TRACKS RUNNING PARALLEL TO SLOPE) AT A TACKLER, NETTING, OR REPLACED WITH PROPERLY ANCHORED EROSION MATTING.
- PLACEMENT OF SEED AND MULCH SHALL OCCUR WITHIN 48 HOURS OF PLACEMENT OF TOPSOIL AND COMPLETION OF FINAL GRADING NOT WITHSTANDING STABILIZATION REQUIREMENTS ELIMINATED IN THIS PLAN.
- ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED WITHIN 30 DAYS AFTER FINAL SITE STABILIZATION OR AFTER THE TEMPORARY MEASURES ARE NO LONGER NEEDED, UNLESS OTHERWISE AUTHORIZED.

- STABILIZATION**
 - ALL AREAS OF DISTURBANCE MUST HAVE TEMPORARY OR PERMANENT STABILIZATION WITHIN 14 DAYS AFTER THIS TIME. ANY DISTURBANCE IN THE AREA MUST BE STABILIZED AT THE END OF EACH WORK DAY.
 - THE FOLLOWING EXCEPTIONS APPLY:
 - STABILIZATION IS NOT REQUIRED IF WORK IS TO CONTINUE IN THE AREA WITHIN THE NEXT 24 HOURS AND THERE IS NO PRECIPITATION FORECAST FOR THE NEXT 24 HOURS.
 - STABILIZATION IS NOT REQUIRED IF THE WORK IS OCCURRING IN A BELT-CONTAINED EXCAVATION (E.G. NO OUTLET) WITH A DEPTH OF 2 FEET OR GREATER (E.G. HOUSE FOUNDATION EXCAVATION, UTILITY TRENCHES).
- MAINTENANCE MUST BE PERFORMED AS NECESSARY TO ENSURE CONTINUED STABILIZATION. EXCEPT AS NOTED BELOW, ALL SITES SHALL BE SEEDED AND STABILIZED WITH EROSION CONTROL MATERIALS, SUCH AS MULCH OR ROLLED EROSION CONTROL PRODUCTS, INCLUDING AREAS WHERE CONSTRUCTION HAS BEEN SUSPENDED OR SECTIONS COMPLETED.
 - ON THE CUT SIDE OF ROAD DITCHES SHALL BE STABILIZED IMMEDIATELY WITH ROCK RIP-RAP OR OTHER NON-ERODIBLE LINERS (E.G. RECP) OR WHERE APPROPRIATE, VEGETATIVE MEASURES SUCH AS SOD.
 - FOR ACTIVE CONSTRUCTION AREAS SUCH AS BORROW OR STOCKPILE AREAS, ROADWAY IMPROVEMENTS AND AREAS WITHIN 50 FT. OF A BUILDING UNDER CONSTRUCTION, A DOWN-SLOPE PERIMETER SEDIMENT CONTROL SYSTEM, CONSIDERING, FOR EXAMPLE, OF SILT FENCING, SHALL BE INSTALLED AND MAINTAINED TO CONTAIN SOIL. EXPOSED DISTURBED AREAS ADJACENT TO A CONVEYANCE THAT PROVIDES RAPID OFF SITE DISCHARGE OF SEDIMENT, SUCH AS A CUT SLOPE AT AN ENTRANCE, SHALL BE COVERED WITH PLASTIC OR GEOTEXTILE TO PREVENT SOIL LOSS UNTIL IT CAN BE STABILIZED. STABILIZED CONSTRUCTION ENTRANCES SHALL BE MAINTAINED TO CONTROL VEHICLE TRACKING MATERIAL OFF SITE.
 - TEMPORARY SEDIMENT TRAPPING DEVICES SHALL NOT BE REMOVED UNTIL PERMANENT STABILIZATION IS ESTABLISHED IN ALL CONTRIBUTING DRAINAGE AREAS. SIMILARLY, STABILIZATION SHALL BE ESTABLISHED PRIOR TO CONVERTING SEDIMENT TRAPPING BASINS INTO PERMANENT POST-CONSTRUCTION STORMWATER MANAGEMENT PRACTICES.
 - STABILIZATION MEASURES SHALL BE APPLIED TO EARTH STRUCTURES SUCH AS DAMS, DIKES, AND OVERSPILLS IMMEDIATELY AFTER INSTALLATION.
 - ALL SLOPES STEEPER THAN 3:1 (H:V), OR 33.3%, AS WELL AS PERIMETER DIKES, SEDIMENT BASINS OR TRAPS, AND EMBANKMENTS SHALL, UPON COMPLETION, BE IMMEDIATELY STABILIZED WITH SOD, SEED AND ANCHORED STRAW MULCH, OR OTHER APPROVED STABILIZATION MEASURES (RECP). AREAS OUTSIDE OF THE PERIMETER SEDIMENT CONTROL SYSTEM SHALL NOT BE DISTURBED.

PERMIT NOTICE
A COPY OF THE DISCHARGE PERMIT, THE AUTHORIZATION TO DISCHARGE, A BRIEF DESCRIPTION OF THE PROJECT, AND THE LOCATION WHERE THE EROSION PREVENTION AND SEDIMENT CONTROL PLAN IS AVAILABLE SHALL BE POSTED AT A LOCATION ON THE PROJECT SITE THAT IS VISIBLE TO THE PUBLIC.

SPECIAL WINTER EPSC PLAN REQUIREMENTS

- STABILIZED ACCESS POINTS SHALL BE ENLARGED TO PROVIDE FOR SNOW STOWING WHILE STILL MAINTAINING EFFECTIVE SEDIMENT CONTROL. PACKED SNOW AND ICE MAY NEED TO BE REMOVED AND ADDITIONAL STONE PLACED TO MAINTAIN THE LOOSE STONE SURFACE AT STABILIZED CONSTRUCTION SITES.
- BASED UPON THE WINTER ACTIVITIES PROPOSED, THE ON-SITE PLAN COORDINATOR SHALL DEVELOP A SNOW MANAGEMENT PLAN THAT SHALL INCLUDE AT A MINIMUM:
 - ADEQUATE SIZE FOR SNOW STORAGE AREAS
 - SNOW STORAGE AREAS LOCATED DOWN GRADIENT OF AREAS OF PLANNED DISTURBANCE
 - CONTROL OF INWIND WINDROFF
 - PROHIBITING STORAGE OF SNOW IN STORMWATER TREATMENT STRUCTURES
 - A MINIMUM 20 FOOT BUFFER BETWEEN PERIMETER CONTROL DEVICES TO ALLOW FOR SNOW CLEARING AND MAINTENANCE
- IN AREAS OF DISTURBANCE WITHIN 100 FT. OF A RECEIVING WATER, THE FOLLOWING MUST BE INSTALLED ACROSS THE SLOPE, DOWN GRADIENT OF THE EARTH DISTURBANCE:
 - FILTER SOCKS OR STRAW WATTLES SHALL BE PLACED IN FRONT OF SILT FENCE OR EROSION CONTROL BERMS
 - SILT FENCE SHALL BE USED IN CONJUNCTION WITH EROSION CONTROL BERMS
 - A SINGLE ROW OF REINFORCED SILT FENCE
- THE ON-SITE PLAN COORDINATOR INSPECTIONS SHALL INCLUDE MAINTENANCE OF DRAINAGE STRUCTURES TO INSURE THAT THEY ARE OPEN AND FREE OF SNOW AND ICE DAMS.
- SILT FENCE AND OTHER PRACTICES REQUIRING EARTH DISTURBANCE SHALL BE INSTALLED AHEAD OF GROUND FREEZING. IF PRACTICES MUST BE INSTALLED OR MAINTAINED AFTER GROUND FREEZING, NO PROZEN MATERIAL SHALL BE USED IN THE CONSTRUCTION OF BERMS, DIKES, OR INSTALLATION OF SILT FENCE.
- WHERE MULCH IS USED FOR TEMPORARY STABILIZATION, IT SHALL BE APPLIED AT A MINIMUM OF 2 INCHES WITH AN 80-90% COVER. TO ENSURE COVER OF DISTURBED SOIL, IN ADVANCE OF A MELT EVENT, AREAS OF DISTURBED SOIL MUST BE STABILIZED PRIOR TO ANY RUNOFF PRODUCING EVENTS, WITH THE FOLLOWING EXCEPTION:
 - STABILIZATION IS NOT REQUIRED IF THE WORK IS OCCURRING IN A BELT-CONTAINED EXCAVATION (E.G. NO OUTLET) WITH A DEPTH OF 2 FEET OR GREATER (E.G. HOUSE FOUNDATION EXCAVATION, UTILITY TRENCHES), PROVIDED ANY OVERSTRENGTH, IF NECESSARY IS CONDUCTED AS REQUIRED.
- PRIOR TO STABILIZATION, SNOW OR ICE MUST BE REMOVED TO THE EXTENT PRACTICABLE.
- BEFORE INTERIOR CONSTRUCTION OR BEFORE WINTER CONTINUES, OR WHERE VEHICLES OR EQUIPMENT TRAFFIC ASSOCIATED IS EXPECTED, A STABILIZED WORK AREA AROUND THE PERIMETER OF THE STRUCTURE SHALL BE STABILIZED WITH CRUSHED STONE OR GRAVEL.





CATCH BASIN INLET PROTECTION
NOTES:
1. INLET PROTECTION TO BE PROVIDED AT ALL CATCHBASINS OR YARD INLETS.
2. THE STONE FILTER SHALL BE INSPECTED FOLLOWING EACH STORM. ACCUMULATED SEDIMENTS SHALL BE REMOVED AND THE STONE REPLACED AS NECESSARY.
3. THE LIMITS OF THE STONE AROUND THE INLET MAY BE MODIFIED BY THE ENGINEER DEPENDING ON THE TOPOGRAPHY DIRECTING RUNOFF TO THE CATCHBASIN.

TURF ESTABLISHMENT

ALL DISTURBED AREAS THAT DO NOT HAVE AN IMPERVIOUS SURFACE (PAVEMENT, SIDEWALKS, ROOFS) OR ARE NOT LANDSCAPED WITH BARK MULCH, SHALL BE STABILIZED WITH NEW GRASS COVER. ALL SEEDING AND MULCHING FOR ESTABLISHING NEW GRASS COVER SHALL BE COMPLETE PRIOR TO SEPTEMBER 15. PLACEMENT OF TOPSOIL, AND THE APPLICATION OF SEED, FERTILIZER, LIME (WHERE APPLICABLE), AND MULCH SHALL BE IN ACCORDANCE WITH THE FOLLOWING:


- A MINIMUM OF 4" OF APPROVED TOPSOIL SHALL BE PLACED IN ALL AREAS. PLACEMENT OF TOPSOIL SHALL NOT BE DONE WHEN THE GROUND IS FROZEN OR PROZEN EXCESSIVELY WET, OR OTHERWISE IN A CONDITION UNDESIRABLE TO THE WORK. FOLLOWING PLACEMENT OF TOPSOIL, THE SURFACE SHALL BE RAKED. ALL STONES, LIMPS, ROOTS, OR OTHER OBJECTUAL MATERIAL SHALL BE REMOVED.
- URBAN SEED MIXTURE SHALL BE SPREAD UNIFORMY IN ALL AREAS AT THE SPECIFIED RATE.
- FERTILIZER SHALL BE APPLIED ONLY AFTER REFORMING A SOIL TEST ON THE REPLACE OR STOCKPILED TOPSOIL, AND BE APPLIED ONLY BASED UPON SOIL TEST RESULTS. LIME SHALL ONLY BE APPLIED AS NEEDED BASED UPON A SOIL PH TEST.
- MULCHING SHALL FOLLOW THE SEEDING OPERATION BY NOT MORE THAN 24 HOURS. MULCH SHALL BE SPREAD UNIFORMY OVER THE AREA AT A MINIMUM RATE OF 2 TONS PER ACRE. SITE CONDITIONS MAY WARRANT THE APPLICATION OF A TACKLER TO HOLD THE MULCH IN PLACE. IF NECESSARY TO RETURN THE MULCH, THE CONTRACTOR SHALL APPLY AN APPROVED TACKLER WITHOUT ADDITIONAL COST TO THE OWNER.
- ALL SLOPES STEEPER THAN 3:1 (H:V) SHALL HAVE EROSION MATTING APPLIED OVER THE SEED. ALL DITCH CENTERLINE GRADES GREATER THAN 1% OR AS SHOWN ON THE PLANS SHALL HAVE EROSION MATTING OVER THE SEED. EROSION CONTROL BLANKET WITH 100% AGRICULTURAL STRAW MATRIX STITCH BOUND WITH DEGRADABLE THREAD BETWEEN TWO BIODEGRADABLE JUTE FIBER NETTING, NORTH AMERICAN GREEN S1500N OR EQUAL.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR A FULL GROWTH OF GRASS IN ALL DISTURBED AREAS TO BE RE-VEGETATED. VEGETATION GROWTH SHALL BE PERMANENT AND SUFFICIENT TO PREVENT EROSION OF THE UNDERLYING SOIL UNDER ALL CONDITIONS OF PRECIPITATION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING AND CARING FOR SEEDING, MULCHING, AND AREAS OF ESTABLISHED VEGETATION UNTIL FINAL ACCEPTANCE OF THE WORK BY THE OWNER.
- HEALTHY EXISTING TREES ON AND ADJACENT TO THE DISTURBED AREAS SHALL BE SAVED AND PROTECTED AS ORDERED BY THE ENGINEER.
- OPEN CUT AREAS SHALL BE MULCHED OUTSIDE OF ACTUAL WORK AREAS, AND HAY BALE MATS BE EMPLOYED TO CONFINE SHEET WASH AND RUNOFF TO THE IMMEDIATE OPEN AREA AS ORDERED BY THE ENGINEER.
- AT COMPLETION OF GRADING, SLOPES, DITCHES, AND ALL DISTURBED AREAS SHALL BE SMOOTH AND FREE OF POCKETS WITH SUFFICIENT SLOPE TO ENSURE DRAINAGE. THE SILT FENCES, MATTED DITCHES, AND OTHER EROSION CONTROL MEASURES SHALL BE MAINTAINED AND REPAIRED BY THE CONTRACTOR PRIOR TO AND AFTER EVERY RAINFALL OR AS ORDERED BY THE ENGINEER UNTIL ALL DISTURBED AREAS HAVE BEEN PLANTED OR GRASSED AND APPROVED BY THE ENGINEER.
- THE MAINTENANCE OF THE EROSION CONTROL DEVICES WILL INCLUDE THE REMOVAL OF ANY ACCUMULATED SEDIMENTATION.



- EROSION MATTING WILL BE USED ON SLOPES STEEPER THAN 3:1 (H:V) OR AS SHOWN ON THE PLANS.
- PREPARE SLOPE BEFORE INSTALLING MATTING, INCLUDING ANY NECESSARY APPLICATION OF LIME, FERTILIZER, AND SEED. SOIL SURFACE SHALL BE GRADUALLY SMOOTHED WITHOUT ROOTS, STONES OR OTHER PROTRUSIONS THAT WILL PREVENT THE MATTING FROM BEING APPLIED IN FULL CONTACT WITH THE SOIL SURFACE.
- BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE MATTING IN A 6" DEEP X 6" WIDE TRENCH WITH APPROXIMATELY 12" OF MATTING EXTENDED BEYOND THE UPLAND PORTION OF THE TRENCH. ANCHOR THE MATTING WITH A ROW OF STAPLES TAKES APPROXIMATELY 12" APART IN THE BOTTOM OF THE TRENCH. BACKFILL AND COMPACT THE TRENCH AFTER STAPLING. APPLY SEED TO COMPACTED SOIL AND FOLD REMAINING 1/2 PORTION OF MATTING BACK OVER SEED AND COMPACTED SOIL. SECURE MATTING OVER COMPACTED SOIL WITH A ROW OF STAPLES SPACED APPROXIMATELY 12" APART ACROSS THE WIDTH OF THE MATTING.
- ROLL THE MATTING [A] DOWN OR [B] HORIZONTALLY ACROSS THE SLOPE. INSURE THAT THE APPROPRIATE SIDE OF THE MATTING CONTACTS THE SOIL SURFACE. MATTING MUST BE SECURELY FASTENED TO SOIL SURFACE BY PLACING STAPLES TAKES IN APPROPRIATE LOCATIONS AS SHOWN IN THE MANUFACTURER'S STAPLE PATTERN GUIDE FOR THE PARTICULAR PRODUCT AND APPLICATION. IN LOOSE SOIL CONDITIONS, THE USE OF STAPLES OR STAKE LENGTHS GREATER THAN 4" MAY BE NECESSARY TO PROPERLY SECURE THE MATTING.
- THE SIDES OF CHANNELS, INCLUDING MATTING BEING STARTED WITH APPROXIMATELY 6" OVERLAP DEPENDING ON MATTING TYPE, AND CONCLUSIVE MATTING APPLIED DOWN THE SLOPE MUST BE PLACED OVER OVERLAP (SHINGLE STYLE) WITH THE UPPER OVERLAPPED AREA, APPROXIMATELY 12" APART ACROSS ENTIRE MATTING WIDTH.

EROSION MATTING FOR SLOPES

EROSION MATTING FOR CHANNELS



| URBAN MIX GRASS SEED | | |
|----------------------|----------|---------------------------|
| NO. #1 WEIGHT | PER ACRE | TYPE OF SEED |
| 37.5 | 40 | ORCHARD GRASS |
| 37.5 | 37.5 | HELMHOLDT BLUEGRASS |
| 37.5 | 37.5 | WINTER WHEAT PERSONAL VUE |
| 100 | 100 | 100% PURE PER ACRE |

LANDS OF
HINESBURG CENTER, LLC
VT Route 116 Hinesburg, VT

EROSION PREVENTION AND SEDIMENT CONTROL DETAILS

LD Lamoureux & Dickinson
Consulting Engineers, Inc.
14 Main Street, Suite 117, 05442
802-878-4450 www.LDengineering.com

| | |
|--------------|----------|
| Project No. | 19054 |
| Survey | N/A |
| Design | NOISRD |
| Drawn | DLH |
| Checked | FLD |
| Date | 5/11/22 |
| Scale | AS NOTED |
| Sheet Number | 9D |