


PROPOSED SUBDIVISION, LASTER PROPERTY HINESBURG, VERMONT







LOCAITON MAP

SCALE: 1" = 2,500'

ZONING MAP

AERIAL PHOTO

CCALC: 1" - 500'

CONSULTANTS

CIVIL ENGINEER: ENGINEERING VENTURES, PC 208 FLYNN AVE, SUITE 2A BURLINGTON, VT 05401

LAND SURVEYOR:
VERMONT MAPPING & SURVEY CO., LLC
8 ESSEX WAY, SUITE 200B
ESSEX JUNCTION, VT 05452

LANDSCAPE ARCHITECT: WAGNER HODGSON 7 MARBLE AVENUE BURLINGTON, CT 05401

TRAFFIC CONSULTANT:
WALL CONSULTANT GROUP
2139 S 1260 W
SALT LAKE CITY, UT 84119-1464

ARCHITECT: TRUEX CULLINS 209 BATTERY STREET BURLINGTON, VT 05401

OWNER/APPLICANT

JOSEPH LASTER 1139 LANIER BLVD ATLANTA, GA 30306 (404) 822-6990

SUBJECT PROPERTY

PARCEL ID: 17-22-62.100
LOCATION: EAST SIDE OF MECHANICSVILLE ROAD
BETWEEN HAWK LANE AND THE TOWN CEMETERY

ZONING DISTRICT DIMENSIONAL STANDARDS

Desidential 4 District		Proposed							
Residential 1 District	Required	Lot 1	Lot 2	Lot 3	Lot 4	Lot 5	Lot 6	Lot 7	Lot 8
Lot Area	6,000-sf minimum	36,452-sf	17,374-sf	19,288-sf	20,451-sf	18,469-sf	20,745-sf	18,081-sf	13,189-sf
Lot Frontage	60-ft minimum	72.18-ft	90.04-ft	104.33-ft	104.81-ft	104.33-ft	104.79-ft	104.00-ft	114.71-ft
Lot Depth	100-ft minimum	249.90-ft	189.31-ft	189.31-ft	171.15-ft	170.48-ft	204.30-ft	200.22-ft	100.00-ft
Front Setback	10-ft (from ROW edge)	10-ft	10 -ft	10-ft	10-ft	10-ft	10-ft	10-ft	10-ft
Side Setback	10-ft	10-ft	10-ft	10-ft	10-ft	10-ft	10-ft	10-ft	10-ft
Rear Setback	10-ft	10-ft	10-ft	10-ft	10-ft	10-ft	10 -ft	10-ft	10-ft
Lot Coverage (max.)	60%	11%	20%	35%	35%	35%	35%	35%	35%

PLAN SHEET REFERENCE

- C1.0 OVERALL EXISTING CONDITIONS PLAN
 C1.1 EXISTING CONDITIONS & DEMOLITION PLAN
- C2.1 SITE LAYOUT PLAN
 C2.2 SITE GRADING & UTILITY PLAN
- C2.3 EROSION PREVENTION & SEDIMENT CONTROL PLAN
- C2.4 SOILS MANAGEMENT PLAN
 C3.1 ROADWAY PLAN AND PROFILE
- C3.2 TYPICAL ROADWAY CROSS SECTION
- C4.0 WATER DETAILS & NOTES
 C4.1 SANITARY DETAILS & NOTES
- C4.2 SITE DETAILS
- C4.3 STORMWATER DETAILS (1 of 2) C4.4 STORMWATER DETAILS (2 of 2)
- C4.4 STORMWATER DETAILS (2 of 2)
 C4.5 EROSION PREVENTION & SEDIMENT CONTROL DETAILS & NOTES

ENGINEERING VENTURES PC
208 Flynn Avenue, Suite 2A, Burlington, VT 05401 s 802-863-6225
85 Mechanic Street, Suite E2-3, Lebanon, NH 03766 s 603-442-9333

414 Union Street, Schenectady, NY 12305 s 518-630-9614

www.engineeringventures.com

JOE LASTER

1139 Lanier Boulevard Atlanta, GA 30306 404.822.6990 Project Title:

Sheet Title:


PROPOSED SUBDIVISION LASTER PROPERTY


Cover Sheet


TOWN OF HINESBURG, CHITTENDEN COUNTY, VERMONT


EV Project #	20542	No.	Description	Date
Drawn By:	HKW	3	TOWN DEVELOPMENT REVIEW BOARD COMMENT RESPONSE	05/25/2023
Checked By:	KW			
Scale:	as noted			
Date:	04/01/2022			


C0.0

















SCALE: HORIZ. 1" = 30' VERT.: 1" = 15'

Sheet Title:




JOE LASTER 1139 Lanier Boulevard Atlanta, GA 30306

404.822.6990

Roadway Plan & Profile PROPOSED SUBDIVISION Project Title: LASTER PROPERTY


TOWN OF HINESBURG, CHITTENDEN COUNTY, VERMONT

EV Project #	20542	No.	Description	Date
Drawn Dv.	HKW	1	TOWN & ANR STORMWATER COMMENT RESPONSE	04/12/2023
Drawn By:	ПСЛ	3	TOWN DEVELOPMENT REVIEW BOARD COMMENT RESPONSE	05/25/2023
Checked By:	KW			
Scale:	as noted			
Scale.	as noteu			
Date:	03/01/2023			



TYPICAL ROADWAY SECTION, STA 2+00

SCALE: 1" =



ENGINEERING VENTURES PC
208 Flynn Avenue, Suite 2A, Burlington, VT 05401 s 802-863-6225
85 Mechanic Street, Suite E2-3, Lebanon, NH 03766 s 603-442-9333 414 Union Street, Schenectady, NY 12305 s 518-630-9614


www.engineeringventures.com


JOE LASTER	
1139 Lanier Boulevard Atlanta, GA 30306 404.822.6990	

iue:	Typical Roadway Cross Section
Title:	PROPOSED SUBDIVISION
	LASTER PROPERTY
	TOWN OF HINESBURG, CHITTENDEN COUNTY, VERMONT

EV Project # 20542	No.	Description	Date
Drawn By: HKW			
Checked By: KW			
Scale: 1" = 5'			
Date: 03/01/2023			

C3.2





TOWN OF HINESBURG DEMAND FLOW BASIS

Existing Wastewater Design Flows source: Vermont Wastewater System & Potable Water Supply Rule, dated April 2019 per table 8-1 for systems receiving 50,000 gpd or more of flow Single Family Home 210 gal/day per living unit 7 living units 1470 gpd Accessory Structure 210 gal/day per living unit 1 living unit 210 gpd Total 1680 gpd

			,			
Existing Water Design Flows source: Vermont Water Supply Rule, dated April 2019 per table A2-1 for Single Family Dwellings						
Single Family Home	150 gal/day per bedroom	3 bedrooms	450 gpd			
Accessory Structure	150 gal/day per bedroom	2 bedrooms	300 gpd			
subtota	for (7) single family homes & acc	cessory structure	3450 gpd			
Total	, with 10% reduction applied for l	ow flow fixtures	3105 gpd			

	Proposed Wastewater Design	n Flows	
	t Wastewater System & Potable Water able 8-1 for systems receiving 50,000 g	• • • •	pril 2019
Single Family Home	210 gal/day per living unit	8 living units Total	1680 gpd 1680 gpd

Proposed Water Design Flows							
9	source: Vermont Water Supply Rule, dated April 2019						
	per table A2-1 for Single Family Dwellings						
Single Family Home	150 gal/day per bedroom	3 bedrooms	450 gpd				
Single Family Home	150 gal/day per bedroom	2 bedrooms	300 gpd				
subtotal for (7) 3-bedroom homes & (1) 2-bedroom home 3450							
Total	, with 10% reduction applied for	ow flow fixtures	3105 gpd				

VT ANR DEMAND FLOW BASIS

Existing Wastewater Design Flows							
source: Vermont Wastewater System & Potable Water Supply Rule, dated April 2019 per table 8-1 for systems receiving 50,000 gpd or more of flow							
·							
Single Family Home	210 gal/day per living unit	1 living unit	210 gpd				
Accessory Structure	210 gal/day per living unit	1 living unit	210 gpd				
		Total	420 gpd				

		iota	ı 420 gpa
Existing Water Design Flows			
source: Vermont Wastewater System & Potable Water Supply Rule, dated April 2019			
*per table 8-1 for systems serving 20 or more living units			
** per 1-803(d)(1) with 2 people per bedroom			
Single Family Home*	360 gpd	for a 3-bedroom living unit	360 gpd
Accessory Structure**	70 gpd/p	erson/bedroom	280 gpd
2 bedrooms			
2 people/bedroom			
		Tota	640 gpd

Existing Water Design Flows			
source: Vermont Water Supply Rule, dated April 2019			
per table A2-1 for Single Family Dwellings			
Single Family Home	150 gal/day per bedroom	3 bedrooms	450 gpd
Accessory Structure	150 gal/day per bedroom	2 bedrooms	300 gpd
Total, with 10% reduction applied for low flow fixtures			675 gpd

Proposed Wastewater Design Flows			
source: Vermont Wastewater System & Potable Water Supply Rule, dated April 2019			
per table 8-1 for systems receiving 50,000 gpd or more of flow			
Single Family Home 210 gal/day per living unit 1 living unit 210 gpd			
Total for (8) single family homes 1680 gpd			1680 gpd

Proposed Water Design Flows			
source: Vermont Wastewater System & Potable Water Supply Rule, dated April 2019			oril 2019
*per table 8-1 for systems serving 20 or more living units			
** per 1-803(d)(1) with 2 people per bedroom			
Single Family Home*	360 gpd	for a 3-bedroom living unit	360 gpd
Single Family Home**	70 gpd/p	erson/bedroom	280 gpd
2 bedrooms			
2 people/bedroom			
Tota f	or (7) 3-bedroon	n homes and (1) 2-bedroom home	2800 gpd

Proposed Water Design Flows source: Vermont Water Supply Rule, dated April 2019 per table A2-1 for Single Family Dwellings			
Single Family Home	150 gal/day per bedroom	3 bedrooms	450 gpd
Accessory Structure	150 gal/day per bedroom	2 bedrooms	300 gpd
subtotal for (7) 3-bedroom homes and (1) 2-bedroom home			3450
Total, with 10% reduction applied for low flow fixtures			3105 gpd

SANITARY SEWER NOTES

CONTRACTOR SHALL CONFORM TO GUIDELINES DETAILED IN THE VERMONT STATE SPECIFICATIONS. CONTRACTOR IS RESPONSIBLE FOR READING AND FOLLOWING THE FULL COMPLETE EDITION

A. THE BUILDING SEWER SHALL BE CONSTRUCTED IN A MANNER WHICH WILL PREVENT LEAKING,

B. SIZING AND SLOPE: MINIMUM BUILDING SEWER SIZE IS 4 INCHES (UNLESS SHOWN ON THE PLAN) AND A MINIMUM SLOPE IS 1/4" PER FOOT.

BREAKING OR CLOGGING.

C. CLEANOUTS: CLEANOUTS SHALL BE PROVIDED AT EACH HORIZONTAL CHANGE IN DIRECTION OF THE BUILDING SEWER GREATER THAN 45 DEGREES AND WHERE INDICATED ON THE DESIGN DRAWINGS. BUILDING SEWER CHANGES IN DIRECTION WHICH EXCEED 45 DEGREES SHOULD BE MADE WITH TWO 45 DEGREE ELLS OR LONG SWEEP FITTINGS. MANHOLES ARE ACCEPTABLE IN LIEU OF CLEANOUTS. WHERE BUILDING SEWERS ARE TO BE INSTALLED AT A DEPTH OF LESS THAN 3 FEET UNDER DRIVEWAYS ARE ANTICIPATED, EXTRA HEAVY CAST IRON PIPE SHALL BE

D. LEAKAGE: BUILDING SEWERS SHALL MEET THE LEAKAGE STANDARDS PRESCRIBED IN THE STATE OF VERMONT SPECIFICATIONS (EPR- CHAPTER 1). SEE BELOW FOR MORE DETAIL. E. SLOPE, VELOCITY: ALL GRAVITY SEWER LINES SHALL BE INSTALLED WITH NOT LESS THAN THE

SLOPES SHOWN BELOW: <u>PIPE SIZE (INCHES)</u> SLOPE (FEET/100 FEET)

F. CHANGES IN PIPE SIZE: WHEN A SMALLER SEWER JOINS A LARGE ONE, THE INVERT OF THE LARGER SEWER SHALL BE LOWERED SUFFICIENTLY TO MAINTAIN THE SAME ENERGY GRADIENT.

G. MATERIAL: PVC SDR 35, ASTM D3034, WITH PUSH-ON GASKETED JOINTS. GASKETS SHALL CONFORM TO ASTM D3212. SEWER JOINTS SHALL BE CONSTRUCTED TO MINIMIZE INFILTRATION AND TO PREVENT THE ENTRANCE OF ROOTS INTO THE SYSTEM.

H. TRENCHING: LEDGE, ROCK, BOULDERS AND LARGE STONES SHALL BE REMOVED TO PROVIDE A MINIMUM CLEARANCE OF FOUR INCHES BELOW AND ON EACH SIDE OF ALL PIPES. I. BEDDING: SEE TRENCH DETAIL DRAWING FOR MATERIALS. TRENCH BACKFILL SHALL BE OF A SUITABLE NATIVE MATERIAL FREE FROM DEBRIS, FROZEN MATERIAL, LARGE CLODS OR STONES, ORGANIC MATTER, OR OTHER UNSTABLE MATERIALS.


J. LEAKAGE TESTS: UPON COMPLETION OF SEWER LINE CONSTRUCTION, THE SEWER LINE SHALL BE TESTED IN ACCORDANCE WITH THE STATE OF VERMONT SPECIFICATIONS (EPR - CHAPTER 1, appendix "a").

LEAKAGE TESTS FOR GRAVITY SEWERS

PERFORM A PRESSURIZED AIR TEST ON THE GRAVITY LINE IN ACCORDANCE WITH THE VERMONT ENVIRONMENTAL PROTECTION RULES ON EACH SECTION OF THE GRAVITY SEWER. THE ENGINEER SHALL BE GIVEN 72 HOURS NOTICE BEFORE THE TEST IS CONDUCTED. TEST MUST BE

PLUG ALL OPENINGS IN THE TEST SECTION. ADD AIR UNTIL THE INTERNAL PRESSURE OF THE LINE IS RAISED TO APPROXIMATELY 4.0 POUNDS/SQUARE INCH (PSI) GREATER THAN THE AVERAGE PRESSURE OF ANY GROUND WATER. AFTER THIS PRESSURE IS REACHED, ALLOW THE PRESSURE TO STABILIZE. THE PRESSURE WILL NORMALLY DROP AS THE AIR TEMPERATURE STABILIZES. THIS USUALLY TAKES 2 TO 5 MINUTES DEPENDING ON THE PIPE SIZE. THE PRESSURE MAY BE REDUCED TO 3.5 PSI BEFORE STARTING THE TEST.

WHEN THE PRESSURE HAS STABILIZED AND IS AT OR ABOVE THE STARTING TEST PRESSURE OF 3.5 PSI ABOVE THE PIPE, START THE TEST. IF THE PRESSURE DROPS MORE THAN 1.0 PSI DURING THE TEST TIME, THE LINE IS PRESUMED TO HAVE FAILED THE TEST. IF A 1.0 PSI DROP DOES NOT OCCUR WITHIN THE TEST TIME. THE LINE HAS PASSED THE TEST, THE TEST TIME SHALL BE DERIVED FROM THE FOLLOWING TABLE. IF THE SECTION OF LINE TO BE TESTED INCLUDES MORE THAN ONE PIPE SIZE, CALCULATE THE TEST TIME FOR EACH SIZE AND ADD THE TEST TIMES TO ARRIVE AT THE TOTAL TEST TIME FOR THE SECTION.



K. INSTALLATION: PIPE SHALL BE LAID WITH BELL ENDS FACING UPGRADE AND LAYING SHALL START AT THE DOWNGRADE END.

L. WATER LINE SEPARATION

a. Horizontal Separation: Sewers shall be laid flat at least ten feet Horizontally FROM ANY EXISTING OR PROPOSED WATER MAIN. THE DISTANCE SHALL BE MEASURED EDGE TO

WHERE IMPOSSIBLE OR IMPRACTICABLE TO MAINTAIN THE TEN FOOT SEWER/WATER PIPE HORIZONTAL SEPARATION, (DUE TO LEDGE, BOULDERS OR OTHER UNUSUAL CONDITIONS) SEWER TRENCH PROVIDED THAT THE BOTTOM OF THE WATER LINE IS AT LEAST 18 INCHES ABOVE THE TOP OF THE SEWER. WHEREVER IMPOSSIBLE OR IMPRACTICAL TO MAINTAIN THE 18 INCH VERTICAL SEPARATION, THE SEWER LINE SHALL BE CONSTRUCTED USING PRESSURE PIPE TO NORMAL WATER LINE STANDARDS AND PRESSURE TESTED TO 50 PSI FOR 15 MINUTE PRIOR TO BACKFILLING.

b. Crossings: Sewers crossing water mains shall be laid beneath the water main WITH AT LEAST 18 INCHES VERTICAL CLEARANCE BETWEEN THE OUTSIDE OF THE SEWER AND THE OUTSIDE OF THE WATER MAIN. WHEN IT IS IMPOSSIBLE TO MAINTAIN THE 18 INCH VERTICAL

1.) THE CROSSING SHALL BE ARRANGED SO THAT ONE FULL LENGTH OF SEWER IS CENTERED ABOVE OR BELOW THE WATER LINE WITH SEWER JOINTS AS FAR AWAY AS POSSIBLE FROM 2.) THE SEWER PIPE MUST BE CONSTRUCTED TO WATER MAIN STANDARDS FOR A MINIMUM DISTANCE OF 20 FEET EITHER SIDE OF THE CROSSING OR A TOTAL OF THREE PIPE LENGTHS, WHICHEVER IS GREATER: 3.) THE SECTION CONSTRUCTED TO WATER MAIN STANDARDS MUST BE PRESSURE TESTED TO MAINTAIN 50 PSI FOR 15 MINUTES WITHOUT LEAKAGE PRIOR TO BACKFILLING BEYOND ONE FOOT ABOVE THE PIPE TO ASSURE WATER TIGHTNESS;

4.) WHERE A WATER MAIN CROSSES UNDER A SEWER, ADEQUATE STRUCTURAL SUPPORT SHALL BE PROVIDED FOR THE SEWER TO PREVENT DAMAGE TO THE WATER MAIN.

a. DIAMETER: THE MINIMUM DIAMETER OF MANHOLES SHALL BE 48 INCHES; LARGE DIAMETERS ARE PREFERRED FOR CONNECTION TO LARGE DIAMETER SEWERS. A MINIMUM ACCESS DIAMETER OF 24 INCHES SHALL BE PROVIDED. b. Flow Channel: Flow Channels shall be provided in the base of all manholes and THE FLOW CHANNEL THROUGH MANHOLES SHOULD BE MADE TO CONFORM IN SHAPE AND SLOPE TO THAT OF THE SEWERS. c. MANHOLES SHALL BE OF THE PRE-CAST CONCRETE OR POUR-IN PLACE CONCRETE TYPE. MANHOLES SHALL BE WATERPROOFED ON THE EXTERIOR. d. Inlet and outlet pipes shall be joined to the manhole with a rubber-gasketed FLEXIBLE WATERTIGHT CONNECTION THAT ALLOWS DIFFERENTIAL SETTLEMENT OF THE PIPE AND e. ALL MANHOLES SHALL BE TESTED FOR LEAKAGE. LEAKAGE TESTING OF GRAVITY SEWERS UTILIZING THE WATER TESTING PROCEDURES TAKES INTO ACCOUNT THE LEAKAGE FROM ONE MANHOLE IN THE TEST SECTION. OTHERWISE, MANHOLES SHALL BE TESTED FOR LEAKAGE IN ACCORDANCE WITH THE FOLLOWING PROCEDURE:

AFTER THE MANHOLE HAS BEEN ASSEMBLED IN PLACE, ALL LIFTING HOLES AND EXTERIOR JOINTS SHALL BE FILLED WITH AND POINTED WITH AN APPROVED NON-SHRINKING MORTAR. ALL PIPES AND OTHER OPENINGS INTO THE MANHOLE SHALL BE SUITABLY PLUGGED AND THE PLUGS PLACED TO PREVENT BLOWOUT.

EACH MANHOLE SHALL BE CHECKED FOR INFILTRATION BY FILLING WITH WATER TO THE TOP OF THE CONE SECTION. A STABILIZATION PERIOD OF ONE HOUR SHALL BE PROVIDED TO ALLOW FOR ABSORPTION. AT THE END OF THIS PERIOD, THE MANHOLE SHALL BE REFILLED TO THE TOP OF HE CONE, IF NECESSARY, AND THE MEASURING TIME OF AT LEAST SIX HOURS BEGUN. AT THE END OF THE TEST PERIOD, THE MANHOLE SHALL BE REFILLED TO THE TOP OF THE CONE MEASURING THE VOLUME OF WATER ADDED. THIS AMOUNT SHALL BE CONVERTED TO A 24 HOUR RATE AND THE LEAKAGE DETERMINED ON THE BASIS OF DEPTH. THE LEAKAGE FOR EACH MANHOLE SHALL NOT EXCEED ONE GALLON PER VERTICAL FOOT FOR A 24 HOUR PERIOD FOR EXFILTRATION AND THERE SHALL BE NO VISIBLE INFILTRATION. IF AN AIR TEST IF PERFORMED ON THE MANHOLE, INSTEAD OF THE WATER TEST, THE MANHOLE SHALL REMAIN UN-BACKFILLED DOWN TO THE SEWER LINE INVERTS DURING THE AIR TEST.


414 Union Street, Schenectady, NY 12305 s 518-630-9614

www.engineeringventures.com

404.822.6990

LASTER PROPERTY TOWN OF HINESBURG, CHITTENDEN COUNTY, VERMONT

20542 Date Description HKW not to scale 03/01/2023



PROPOSED SUBDIVISION

LASTER PROPERTY

TOWN OF HINESBURG, CHITTENDEN COUNTY, VERMONT

Project Title:

1139 Lanier Boulevard

Atlanta, GA 30306

404.822.6990

208 Flynn Avenue, Suite 2A, Burlington, VT 05401 • 802-863-6225

85 Mechanic Street, Suite E2-3, Lebanon, NH 03766 • 603-442-9333

414 Union Street, Schenectady, NY 12305 * 518-630-9614


www.engineeringventures.com

Checked By:

not to scale

03/01/2023

C4.2



ENGINEERING VENTURES PC

JOE LASTER

JOE LASTER

JOE LASTER


JOE LASTER


Sheet Title:

Stormwater Details (1 of 2)


Project Title:

TOWN OF HINESBURG, CHITTENDEN COUNTY, VERMONT





ORANGE CONSTRUCTION FENCE DETAIL



STONE SIZE: USE AGGREGATE FOR EPSC MEETING REQUIREMENTS OF EARTHWORK SPECIFICATIONS SURFACE WATER - ALL SURFACE WATER FLOWING OR DIVERTED TOWARD CONSTRUCTION ENTRANCE SHALL BE PIPED ACROSS THE ENTRANCE.

MAINTENANCE - THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHT-OF-WAYS. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND. REPAIR AND/OR CLEANOUT ANY MEASURES USED TO TRAP SEDIMENT. TRACKING ONTO PUBLIC RIGHT-OF-WAYS SHALL **NOT** BE ALLOWED. ALL SEDIMENT SPILLED, DROPPED, OR WASHED ONTO PUBLIC RIGHT-OF-WAYS MUST BE REMOVED IMMEDIATELY AND ANY WASH WATER MUST BE CONTAINED AND PROPERLY DISPOSED OF.

PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH RAIN. WHEELS SHALL BE CLEANED TO REMOVE MUD PRIOR TO ENTRANCE ONTO PUBLIC RIGHT-OF-WAY. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH STONE WHICH DRAINS INTO AN APPROVED SEDIMENT

STABILIZED CONSTRUCTION ENTRANCE

MIRAFI 140N FILTER FABRIC OR EQUAL BACKFILL - 6" X 6" WOVEN WIRE FENCE (14 GA. MIN.) EMBED 18" MIN. SECTION A-A - MIRAFI 140N FILTER FABRIC 2'-0" MIN. OR EQUAL FENCE POST 10'-0" MAX.

NOTES:


1. SILT FENCE SHALL BE PRE-FABRICATED EROSION CONTROL FENCE BY MIRAFI OR EQUAL, OR CONSTRUCTED IN PLACE AS SPECIFIED HEREIN.

CONSTRUCTED IN PLACE SILT FENCE: A. WOVEN WIRE FENCE TO BE FASTENED SECURELY TO FENCE POSTS WITH WIRE TIES OR STAPLES. B. FILTER FABRIC TO BE FASTENED SECURELY TO WOVEN WIRE FENCE TIES SPACED EVERY 24" AT TOP OF MID


C. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER, THEY SHALL BE OVERLAPPED BY 6", FOLDED AND

STAPLED. INSPECTION SHALL BE FREQUENT (MINIMUM ONCE A WEEK AND AFTER EVERY RAINFALL). MAINTENANCE SHALL BE PERFORMED AS NEEDED, AND SEDIMENT REMOVED WHEN "BULGES" DEVELOP IN SILT FENCE.

FENCE DETAIL




PROTECTION DETAIL



STRAW FIBER ROLL NOTES INSTALL ROLLED STRAW FIBER ROLL PARALLEL ALONG THE CONTOUR OF THE SLOPE.

2. TO MAXIMIZE SEDIMENT CONTAINMENT WITH THE STRAW FIBER ROLL, PLACE THE INITIAL STRUCTURE AT THE TOP/CREST OF THE SLOPE IF SIGNIFICANT RUNOFF IS EXPECTED FROM ABOVE. IF NO RUNOFF FROM ABOVE IS EXPECTED, THE INITIAL STRAW WATTLE CAN BE INSTALLED AT THE APPROPRIATE DISTANCE DOWNHILL FROM THE TOP/CREST OF THE SLOPE. THE FINAL STRUCTURE SHOULD BE INSTALLED AT OR JUST BEYOND THE BOTTOM/TOE OF THE SLOPE WATTLES SHOULD BE INSTALLED PERPENDICULAR TO THE PRIMARY DIRECTION OF OVERLAND FLOW

STRAW FIBER ROLL - SOIL



THE AREA UNDER EMBANKMENT SHALL BE CLEARED, GRUBBED AND STRIPPED OF ANY VEGETATION AND ROOT MAT. THE POOL AREA SHALL BE CLEARED. THE FILL MATERIAL FOR THE EMBANKMENT SHALL BE FREE OF ROOTS OR OTHER WOODY VEGETATION AS WELL AS OVER-SIZED STONES, ROCKS, ORGANIC MATERIAL OR OTHER OBJECTIONABLE MATERIAL. THE EMBANKMENT SHALL BE COMPACTED BY TRAVERSING WITH EQUIPMENT WHILE IT IS BEING CONSTRUCTED.

MAXIMUM HEIGHT OF EMBANKMENT SHALL BE FIVE (5) FEET, MEASURED AT CENTERLINE OF EMBANKMENT. ALL FILL SLOPES SHALL BE 2:1 OR FLATTER, CUT SLOPES 1:1 OR FLATTER.

ELEVATION OF THE TOP OF ANY DIKE DIRECTING WATER INTO TRAP MUST EQUAL OR EXCEED THE HEIGHT OF EMBANKMENT. 5. STORAGE AREA PROVIDED SHALL BE FIGURED BY COMPUTING THE VOLUME AVAILABLE BEHIND THE OUTLET CHANNEL UP TO AN ELEVATION OF ONE (1) FOOT BELOW THE LEVEL WEIR CREST.

6. FILTER CLOTH SHALL BE PLACED OVER THE BOTTOM AND SIDES OF THE OUTLET CHANNEL PRIOR TO PLACEMENT OF STONE. SECTIONS OF FABRIC MUST OVERLAP AT LEAST ONE (1) FOOT WITH SECTION NEAREST ENTRANCE PLACED ON TOP. FABRIC SHALL BE EMBEDDED AT LEAST SIX (6) INCHES INTO EXISTING

7. STONE USED IN THE OUTLET CHANNEL SHALL BE FOUR (4) TO EIGHT (8) INCH RIP-RAP. TO PROVIDE A FILTERING EFFECT, A LAYER OF FILTER CLOTH SHALL BE EMBEDDED ONE (1) FOOT WITH SECTION NEAREST ENTRANCE PLACED ON TOP. FABRIC SHALL BE EMBEDDED AT LEAST SIX (6) INCHES INTO EXISTING GROUND AT ENTRANCE OF OUTLET CHANNEL.

8. SEDIMENT SHALL BE REMOVED AND TRAP RESTORED TO ITS ORIGINAL DIMENSIONS WHEN SEDIMENT HAS ACCUMULATED TO 1/2 THE DESIGN DEPTH OF THE TRAP. REMOVED SEDIMENT SHALL BE DEPOSITED IN A SUITABLE AREA AND STABILIZED.


THE STRUCTURE SHALL BE INSPECTED AFTER EACH RAIN AND REPAIRED AS NEEDED.

CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER THAT EROSION AND SEDIMENT ARE CONTROLLED. 11. THE STRUCTURE SHALL BE REMOVED AND THE AREA STABILIZED WHEN DRAINAGE AREA HAS BEEN PROPERLY STABILIZED.

12. DRAINAGE AREA FOR THIS PRACTICE IS LIMITED TO 15 ACRES OR LESS.

13. SEDIMENT TRAPS SHALL MEET THE VERMONT HANDBOOK FOR SOIL EROSION AND SEDIMENT CONTROL ON CONSTRUCTION SITES.

TEMPORARY SEDIMENT TRAP W/RIP-RAP OUTLET



SEEDING AND MULCHING OF DISTURBED AREAS SHALL TAKE PLACE WITHIN 48 HOURS OF FINAL

GRADING. MULCH: HAY SHALL NOT BE USED. STRAW MULCH SHALL BE UTILIZED AND SHALL BE APPLIED AT A RATE OF 90-1,000 LBS/1,000 SF. MULCH SHALL NOT BE PLACED ON SLOPES OF GREATER THAN 3:1. SEED IMPREGNATED EROSION CONTROL NETTING SHALL BE USED IN ITS PLACE. SEED: SEEDING SHALL OCCUR

AFTER APRIL 15 AND PRIOR TO SEPTEMBER 15TH IN ORDER TO ESTABLISH A STAND OF GRASS PRIOR TO GROUND FREEZING. SEED SHALL BE IN ACCORDANCE WITH SEED SPECIFICATION ON THIS SHEET. COVER SEED WITH 1 INCH SOIL

UNLESS A HYDROSEEDER IS USED. MULCH ANCHORING: SHALL BE ACCOMPLISHED BY DEGRADABLE MULCH NETTING. USE WHEN SLOPES ARE GREATER THAN 10%. TOPSOIL AND MULCHING NOT TO BE APPLIED IN AREAS OF TRAVEL


URBAN MIX GRASS SEED (FOR USE IN GRASSED LAWN AREAS AROUND BUILDINGS AND PARKING) % BY WEIGHT LBS. LIVE SEED BY ACRE TYPE OF SEED 37.5 CREEPING RED FESCUE 31.3 37.5 KENTUCKY BLUEGRASS WINTER HARDY, PERENNIAL RYE 31.3 37.5

120 LBS. LIVE SEED / ACRE

CONSERVATION MIX GRASS SEED (FOR USE IN ALL OTHER AREAS)			
% BY WEIGHT	LBS. LIVE SEED BY ACRE	TYPE OF SEED	
35	77	CREEPING RED FESCUE	
20	44	KENTUCKY BLUEGRASS	
15	33	CUTTER PERENNIAL RYE	
15	33	ANNUAL RYE GRASS	
10	22	TALL FESCUE	
55	11	WHITE CLOVER	
100	220 LBS. LIVE SEED / ACRE		

SEEDED AND MULCHED AREAS

100



SLOPE SURFACE SHALL BE FREE OF ROCKS, CLODS, STICKS AND GRASS. MATS/ BLANKETS SHALL HAVE GOOD SOIL CONTACT. APPLY PERMANENT SEEDING BEFORE PLACING BLANKETS. LAY BLANKETS LOOSELY AND STAKE OR STAPLE TO MAINTAIN DIRECT CONTACT WITH THE SOIL. DO NOT STRETCH.

EROSION CONTROL BLANKET

GENERAL EROSION CONTROL NOTES

THE CONTRACTOR SHALL DESIGNATE AN "ON-SITE EROSION CONTROL PLAN COORDINATOR" WHO WILL BE PRESENT ON-SITE FROM DAY-TO-DAY, AND SHALL BE RESPONSIBLE FOR ENSURING THAT THE EROSION CONTROL MEASURES REQUIRED BY THE EROSION CONTROL PLAN, DETAILS AND NOTES, ARE PROPERLY INSTALLED AND MAINTAINED. THE ONSITE EROSION CONTROL PLAN COORDINATOR SHALL KEEP A WRITTEN RECORD OF INSPECTIONS AND MAINTENANCE OF EROSION CONTROL FEATURES. A COPY OF THESE PLANS AND INSPECTION/MAINTENANCE RECORDS SHALL BE KEPT ONSITE AT ALL TIMES.

THE CONTRACTOR SHALL NOTIFY THE TOWN OF HINESBURG DEPARTMENT OF PUBLIC WORKS DIVISION AT LEAST 24-HOURS PRIOR TO ANY EARTH DISTURBING ACTIVITIES AND SUBMIT THE NAME AND CONTACT INFORMATION (CELL PHONE AND EMAIL) OF THE ON-SITE EROSION CONTROL COORDINATOR FOR THE PROJECT. THE CONTRACTOR IS RESPONSIBLE FOR POSTING THE EROSION PREVENTION AND SEDIMENT CONTROL PLAN NOTICE IN A VISIBLE LOCATION AT ALL TIMES DURING EARTH DISTURBANCE.

DISTURBANCE LIMITS ARE TO BE MARKED, AND THE FOLLOWING MANAGEMENT PRACTICES INSTALLED, PRIOR TO BEGINNING EARTHWORK IN ANY GIVEN AREA; SILT FENCE, CONSTRUCTION ENTRANCE, INLET PROTECTION & TREE PROTECTION FENCING.

COMPLY WITH VERMONT STATE GENERAL CONSTRUCTION PERMIT CONDITIONS. ALL EROSION CONTROL MEASURES SHALL BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH THE MOST RECENT VERSION OF THE VERMONT DEC LOW RISK SITE HANDBOOK FOR EROSION PREVENTION & SEDIMENT CONTROL.

DURING THE NON-WINTER CONSTRUCTION SEASON, ALL DISTURBED AREAS ARE TO BE STABILIZED (TEMPORARY OR FINAL) WITHIN 14-DAYS OF INITIAL DISTURBANCE. AFTER THIS TIME, ANY DISTURBANCE WITHIN THIS WORK AREA MUST BE STABILIZED AT THE END OF EACH WORK DAY, WITH THE FOLLOWING EXCEPTIONS:

A. STABILIZATION IS NOT REQUIRED IF WORK IS TO CONTINUE IN THE AREA WITHIN 24 HOURS AND NO PRECIPITATION IS FORECAST DURING THAT PERIOD

B. WORK IS OCCURRING WITHIN A SELF-CONTAINED EXCAVATION, 2-FEET OR MORE IN DEPTH

6. THE PERIOD BETWEEN NOVEMBER 1ST AND APRIL 15TH IS CONSIDERED THE 'WINTER CONSTRUCTION PERIOD'. IF SOILS WILL BE EXPOSED AFTER NOVEMBER 1ST, A PLAN FOR WINTER CONSTRUCTION MUST BE DEVELOPED BY THE CONTRACTOR AND SUBMITTED TO THE ENGINEER ON OR BEFORE OCTOBER 1ST. THE CONTRACTOR SHALL ENSURE SEDIMENT CONTROL IS INSTALLED PRIOR TO THE SOIL FREEZING. AN INSPECTION WILL BE REQUIRED IF THE PROJECT IS COMPLETED DURING THE WINTER MONTHS TO ENSURE THE SITE IS SECURED FOR THE REMAINDER OF THE SEASON.

DURING THE WINTER CONSTRUCTION SEASON, ANY NEW DISTURBANCE MUST BE STABILIZED (TEMPORARY OR FINAL) AT THE END OF EACH WORK DAY, WITH THE FOLLOWING EXCEPTIONS:

A. STABILIZATION IS NOT REQUIRED IF WORK IS TO CONTINUE IN THE AREA WITHIN 24 HOURS AND NO PRECIPITATION IS FORECAST DURING THAT PERIOD

B. WORK IS OCCURRING WITHIN A SELF-CONTAINED EXCAVATION, 2-FEET OR MORE IN DEPTH.

IN NO CASE SHALL SOIL BE EXPOSED FOR MORE THAN 14 DAY WITHOUT BEING STABILIZED.

ALL DISTURBED AREAS ARE TO BE PERMANENTLY STABILIZED WITHIN 48 HOURS OF FINAL GRADING 10. THE PERIMETER OF THE SITE AND ALL BMPS SHALL BE INSPECTED AT THE END OF EACH WORK DAY TO ENSURE SEDIMENT DOES NOT LEAVE THE SITE. IF SEDIMENT HAS TRAVELED BEYOND THE PROJECT LIMITS, IT SHALL BE RELOCATED IN AN UPGRADIENT AREA ON SITE AT THE END OF EACH WORK DAY.

11. ALL STABILIZATION INVOLVING SEEDING IS TO BE COMPLETED BY SEPTEMBER 15TH.

12. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DAILY INSPECTION OF THE ADJACENT ROADWAYS FOR OFF-SITE TRACKING OF SOIL MATERIALS. SOIL STONE, AND DEBRIS FOUND LEAVING THE SITE ARE TO BE REMOVED (WHEN FOUND) BY SWEEPING AT THE END OF EACH CONSTRUCTION DAY, OR MORE FREQUENTLY WHEN NEEDED TO PREVENT IMPACTS TO ADJACENT ROADS AND SIDEWALKS.

13. IF DEWATERING IS REQUIRED FOR CONSTRUCTION, THE CONTRACTOR MUST UTILIZE SEDIMENT FILTER BAGS (OR ALTERNATE

APPROVED BY THE ENGINEER) TO PREVENT DISCHARGE OF SEDIMENT-LADEN WATER OFF SITE. 14. EXCAVATED MATERIAL FROM EARTH EXCAVATION AND DITCH DIGGING SHALL BE PLACED ONSITE IN A LOCATION TO BE APPROVED OF BY THE OWNER AND/OR THE ENGINEER OR USED FOR PROJECT FILL MATERIAL IF DETERMINED SUITABLE BY THE OWNER'S

15. STOCKPILED MATERIAL (TOPSOIL, BORROW, ETC.) SHALL HAVE SILT FENCE CONSTRUCTED AROUND THE PERIMETER. THE STOCKPILED MATERIAL SHALL BE SEEDED AND MULCHED AS SOON AS POSSIBLE TO PREVENT SOIL EROSION AND SEDIMENTATION OFF SITE. LOCATE STOCKPILES ON THE UPHILL SIDE OF DISTURBED AREAS, IF POSSIBLE. DURING WINDY CONDITIONS, STOCKPILED MATERIAL SHALL BE COVERED OR WATERED APPROPRIATELY TO PREVENT WIND EROSION.

16. SLOPES GREATER THAN 3:1 SHALL HAVE EROSION CONTROL MATTING INSTALLED TO STABILIZE THE SLOPE AND REDUCE THE EROSION POTENTIAL. MATTING SHALL BE BIODEGRADABLE WITH A 12 MONTH LONGEVITY, S150BN AS MANUFACTURED OR APPROVED EQUIVALENT. INSTALL MATTING OVER MULCHED SLOPES SO THAT ALL PARTS ARE IN CONTACT WITH THE SOIL AND MULCH. PIN MATTING WITH WIRE STAPLES 3 FEET O.C. TO ENSURE FULL BONDING WITH SOIL SURFACE. THE SLOPE SURFACES SHOULD BE LEFT SLIGHTLY ROUGHENED AND NOT SMOOTH. IF LARGE AMOUNTS OF OFFSITE WATER WILL DRAIN OVER THESE SLOPES, TEMPORARY DIVERSION SWALES SHALL BE INSTALLED UP SLOPE UNTIL THE SLOPE VEGETATION STABILIZES.

17. THE OWNER SHALL BE NOTIFIED WHEN SITE WORK IS COMPLETED AND THE SITE IS STABILIZED.

WINTER EROSION CONTROL

WINTER CONSTRUCTION PROCEDURES

1. DURING WINTER CONSTRUCTION, INSPECTIONS BY THE ON-SITE PLAN COORDINATOR SHALL OCCUR FOR ANY AREAS NOT FULLY STABILIZATION IS IN PLACE.

2. IN AREAS TO BE STABILIZED BY VEGETATION, ALL SEEDING MUST BE COMPLETED BY SEPTEMBER 15 TO ALLOW GROWTH TO OCCUR PRIOR TO THE GROUND FREEZING. STABILIZATION OF ALL OTHER DISTURBED AREAS SHALL BE COMPLETED BY OCTOBER 15.

ENLARGED ACCESS POINTS, STABILIZED TO PROVIDE FOR SNOW STOCKPILING SHALL BE INSTALLED. LIMITS OF DISTURBANCE SHALL BE MOVED OR REPLACED TO REFLECT BOUNDARY OF WINTER WORK.

SNOW WILL NOT BE PILED WITHIN 25 FEET OF PERIMETER CONTROLS (SUCH AS SILT FENCE) TO ALLOW FOR CLEARING AND MAINTENANCE. SNOW IS TO BE REMOVED FROM ALL STRUCTURAL EROSION PREVENTION AND SEDIMENTATION CONTROL MEASURES FOLLOWING EACH SIGNIFICANT SNOWFALL. NO SNOW STORAGE UP-GRADIENT OF DISTURBANCE. NO SNOW DISPOSAL IN SEDIMENT PONDS/BASINS. IF NECESSARY. SNOW/ICE MUST BE REMOVED PRIOR TO STABILIZATION OF DISTURBED AREAS. ACCESS POINTS

SHALL BE ENLARGED AND STABILIZED TO ALLOW FOR SNOW STOCKPILING. IN AREAS OF DISTURBANCE WITHIN 100 FT OF A RECEIVING WATER, SILT FENCE SHALL BE REINFORCED OR ELSE REPLACED WITH

PERIMETER DIKES, SWALES OR OTHER PRACTICES RESISTANT TO THE FORCES OF SNOW LOADS.

DRAINAGE STRUCTURES SHALL BE KEPT OPEN AND FREE OF SNOW AND ICE DAMS.

8. ALL EROSION PREVENTION AND SEDIMENT CONTROL MEASURES ARE TO BE IN PLACE BY OCTOBER 15, OR IF NOT POSSIBLE, THEN PRIOR TO GROUND FREEZE. MULCH IS TO BE APPLIED AT THE END OF EACH WORKDAY TO ALL EXPOSED AREAS THAT HAVE NOT YET REACHED FINAL GRADE

AT TWICE THE RATE INDICATED IN THE SEEDING AND MULCHING DETAIL FOR THE REGULAR CONSTRUCTION SEASON. MULCH SHALL BE TRACKED IN OR STABILIZED WITH NETTING.

10. TO ENSURE COVER OF DISTURBED SOIL IN ADVANCE OF A MELT EVENT, AREAS OF DISTURBED SOIL MUST BE STABILIZED AT THE END OF EACH WORK DAY, WITH THE FOLLOWING EXCEPTIONS: A. IF NO PRECIPITATION WITHIN 24 HOURS IS FORECAST AND WORK WILL RESUME IN THE SAME DISTURBED AREA WITHIN 24

HOURS. DAILY STABILIZATION IS NOT NECESSARY. B. DISTURBED AREAS THAT COLLECT AND RETAIN RUNOFF, SUCH AS HOUSE FOUNDATIONS OR OPEN UTILITY TRENCHES.

11. SNOW AND ICE SHALL BE REMOVED TO LESS THAN 1" THICKNESS PRIOR TO STABILIZATION.

12. STONE STABILIZATION, 10 TO 20 FT WIDE IN AREAS SUCH AS THE PERIMETER OF BUILDINGS UNDER CONSTRUCTION WHERE CONSTRUCTION VEHICLE TRAFFIC IS ANTICIPATED SHALL BE INSTALLED.

ENGINEERING VENTURES PC

JOE LASTER

Atlanta, GA 30306 404.822.6990

Sheet Title:

Erosion Prevention & Sediment Control Details & Notes

PROPOSED SUBDIVISION LASTER PROPERTY

EV Project # 20542 Description Drawn By: HKW Checked By: not to scale 03/01/2023

C4.5

Date

www.engineeringventures.com

208 Flynn Avenue, Suite 2A, Burlington, VT 05401 s 802-863-6225

85 Mechanic Street, Suite E2-3, Lebanon, NH 03766 s 603-442-9333 414 Union Street, Schenectady, NY 12305 s 518-630-9614

1139 Lanier Boulevard

Project Title:

TOWN OF HINESBURG, CHITTENDEN COUNTY, VERMONT